

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24927-00-01
Spot: SWNWSWNW Sec/Twnshp/Rge: 32-12S-19W
3562 feet from S Section Line, 5029 feet from E Section Line
Lease Name: AMREIN Well #: 4
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3870		200 SX
SURF	8.625	220		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2014 8:30 AM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: JOE STUHL Company: PRAIRIE HAWK WELL SERVICE L Phone: (785) 885-8240

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.
DV Tool at 1516' w/300 sx cement.
Cong- 3770' - 3832' O.A.
Squeezed bottom of hole. Drilled out casing at unknown depth

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2014 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Prairie Hawk ran in hole with tubing to 3484'. Allied rigged to tubing and mixed and pumped 13 sx gel followed by 50 sx cement w/100 # hulls mixed in. Pulled tubing to 2000'. Allied rigged to tubing and mixed and pumped 150 sx cement w/400 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/40 sx cement. Hole standing full. Connected to 8 5/8" casing and pumped 10 sx cement to pressure with 50 psi. Shut in pressure 50 psi.

GPS: 38.96758 -099.46425
3548' FSL 4953' FEL
SE NW SW NW

Remarks: ALLIED CEMENTING CO TICKET # 15561

Plugged through: TBG

District: 04

Signed

KCC WICHITA

(TECHNICIAN)

MAR 18 2014

RECEIVED

MAR 14 2014