

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23484-00-00  
Spot: NESWNWNW Sec/Twnshp/Rge: 15-7S-21W  
800 feet from N Section Line, 650 feet from W Section Line  
Lease Name: BUTCH Well #: 1  
County: GRAHAM Total Vertical Depth: 3743 feet

Operator License No.: 34559  
Op Name: WM KS ENERGY RESOURCES LLC  
Address: 1001 FANNIN, STE 4000  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3742		215 SX
SURF	8.625	221		160 SX
T1	2.875	3350		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2013 12:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BILL ROBINSON Company: ALLIED CEMENT COMPANY Phone: (785) 688-4040

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 5% gel cement, 200 # hulls and 11 sx gel,

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 08/08/2013 12:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3340' and pumped 11 sx of gel. Mixed and pumped 200# hulls w/ 50 sx of 60/40 poz + 5% gel. Pulled tubing to 1784'. Mixed and pumped 175 sx of 60/40 poz + 5% gel. Cement circulated to surface. Hooked up surface pipe and pumped 50 sx cement, pressured to 300 psi. Dug out braiden head and cut off 5' below surface. Capped off surface pipe and backfilled cellar.

Perfs:

Top	Bot	Thru	Comments
3372	3374		

KCC WICHITA  
MAR 10 2014

Remarks: ALLIED OIL AND GAS TICKET # 056987

RECEIVED

Plugged through: TBG

District: 04

Signed   
3/29/14 (TECHNICIAN)

CM

MAR 06 2014