

AFFIDAVIT AND COMPLETION FORM


ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR TXO PRODUCTION CORP. API NO. 15-007,21,069-0000
 ADDRESS 200 W. Douglas, Suite 300 COUNTY Barber
Wichita, KS 67202 FIELD Aetna
 **CONTACT PERSON Harold R. Trapp LEASE Z-Bar Cattle Co.
 PHONE 265-9441

PURCHASER Delhi WELL NO. Z-Bar Cattle Co. "C" #1
 ADDRESS 2150 Fidelity Union Tower WELL LOCATION _____
Dallas, TX 75201 2210 Ft. from East Line and
 330 Ft. from North Line of
 the 8 SEC. 35S TWP. 15W RGE.

DRILLING CONTRACTOR Freeman, Rig #1
 ADDRESS 251 N. Water
Wichita, Kansas 67202



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

PLUGGING CONTRACTOR N/A
 ADDRESS N/A

TOTAL DEPTH 5202 PBDT 5185

SPUD DATE 1-3-81 DATE COMPLETED 2-8-81

ELEV: GR 1797 DF KB 1809

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set - surface, intermediate, production, etc. (New)/(Used) casing.

KCC
 KGS
 PUL

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	24#	1055'		450	
Production		4-1/2"	10.5#	5204'		125 sxs thixotropic cmt 40 bbls mud, 500 gal mud flush, 40 bbl 2% KCl	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF(22 h.)	Miss.	5175-80' & 5160-65'

TUBING RECORD		
Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
Spotted 2 bbls 15% HCl across perfs.	5175-80' & 5160-65'
Acidized w/1500 gals 15% HCl w/clay stabilizer & surfactant & 30 ball sealers. Perfs balled off.	
Attempted to frac @ 25 BPM. Fraced w/10,000# 20/40, 28,500# 10/20, & 343 bbls 2% HCl wtr in 70-quality foam @ 15 BPM	

TEST DATE:	PRODUCTION FORMATION: Miss.
Date of first production 10-30-81	Producing method (flowing, pumping, gas lift, etc.) flowing
RATE OF PRODUCTION PER 24 HOURS	Producing interval(s) 5175-80' & 5160-65'
Oil 3.34 bbls	Gas 42 bbls
Water 12 bbls	Gas:oil ratio N/A
Disposition of gas (vented, used on lease or sold) Sold	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

FIELD: Aetna

Name of lowest fresh water producing stratum Unknown Depth N/A
 Estimated height of cement behind pipe Circulated to pipe

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS-RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOG TOPS</u>				
Herington	2375	-566		
Winfield	2442	-633		
Towanda	2521	-712		
Florence	2611	-802		
Wreford	2709	-900		
Cottonwood	2933	-1124		
Foraker	3058	-1249		
Onaga	3264	-1455		
Indian Cave	3288	-1479		
Wabaunsee	3316	-1507		
Stotler	3469	-1660		
Howard	3568	-1757		
Topeka	3637	-1828		
LeCompton	4008	-2199		
Heebner	4246	-2437		
Toronto	4258	-2449		
Douglas	4278	-2469		
Lansing	4445	-2636		
Swope	4880	-3071		
B/Kansas City	4960	-3151		
Pawnee	5054	-3245		
Cherokee	5106	-3297		
Miss.	5153	-3344		
RTD	5202			
PBD	5185			
DST #1, 5158-5204' (Miss.), w/results as follows:				
IFP/45": 103-144#, weak blow				
ISIP/90": 863#				
FFP/45": 114-186#				
FSIP/90": 740#				
Rec: 65' DM				
Ran O.H. Logs				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Sedgwick SS,

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS District Geologist FOR TXO Production Corp. OPERATOR OF THE Z-Bar Cattle Co. LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. "C" #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 10th DAY OF October 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10th DAY OF November 19 81

PAMELA S. JOLLIFF

STATEWIDE NOTARY PUBLIC

Harvey County, Ks.

My Appt. Expires 9/14/83

(S) Harold R. Trapp

Pamela S. Joliff
NOTARY PUBLIC

MY COMMISSION EXPIRES: 9/14/83