



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

4 - November 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)
15-033-20498.00.00

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1981

Dear Sir:

Mr. David Divine of De Mack Drilling Inc. has requested permission to plug the following described well:

Operator's Full Name: Santa Fe Energy Co.

Complete Address: One Security Park 7200 1-40 West Amarillo Texas 79106

Lease Name: Vernon Well No. 1

Location: C-SW Sec. 17 Twp. 31S Rge. 20W (E) (W)

County: Comanche Total Depth: 5370'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Divine was instructed to plug the well as follows:

The surface casing was cement circulated at 639' it was 8 5/8" 1st plug at 725' with 40 sby of cement to cover stone cwell which was topped 695' to 703' 2nd plug push rubber plug to 600' and pumped 35 sby cement on top of it. 3rd plug 40' to 0' on solid bridge with 10 sby cement. Then put 5 sby in rat hole & 5 sby in mouse hole. Plugging accomplished by Halliburton out of Pratt Kans.

Very truly yours,

Paul Luthi
Conservation Division Agent