

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1968

CONSERVATION DIVISION

Wichita, Kansas

2-26-68

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed February 7, 1968.

Dear Sir:

Mr. Calvin Roberts of Leben Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Western Oil Fields, Inc.

Complete Address: P. O. Box 791, Ponca City, Oklahoma 74601

Lease Name: Sternberger Well No. # 5

Location: C SE NW SE Sec. 10 Twp. 35 Rge. 14 (E)(W) W

County Barber Total Depth 4910' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Roberts was instructed to plug the well as follows:

387' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fill  
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
Conservation Division Agent