

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1965  
6-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name: Davis Ranch Well No. # 2-1

Location: Approx. C W/2 Sec. 1 Twp. 35 Rge. 15 (E)(W) W

County Barber Total Depth 4953' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

120' of 13 3/8" conductore string, cement circulated. 826' of 8 5/8"  
surface pipe, cemented with 125 sacks. Fill hole with drilling mud  
to 300', 1st cementing plug, bridge with hulls, and cement with 25  
sacks. Fill hole with drilling mud to 40', 2nd cementing plug,  
bridge with hulls, and cement with 10 sacks to base cellar. Bridge  
and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent