

CPI

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-21.092-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corporation KCC LICENSE # 5506 4/96  
(owner/company name) (operator's)

ADDRESS 107 N. Market CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 886-5606

LEASE Z-Bar E WELL# 1 SEC. 9 T. 35 R. 15 (East/West)

- NE - NE - NW SPOT LOCATION/QQQQ COUNTY Barber

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2210 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE 8 5/8" SET AT 1005' CEMENTED WITH 400 SACKS

SURFACE CASING SIZE        SET AT        CEMENTED WITH        SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5145' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Attachment

ELEVATION 1800 T.D. 5169 PBD 2265 ANHYDRITE DEPTH         
(G.L. K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Dump sand & fill to 2364' (50' above perms) Place 2 sax cement on sand w/dump bailer. Cut 4 1/2" @ freepoint & TOOH. From surface pump 300# cotton seed hulls, 10 sax gel, 50 sax cement, 10 sax gel, 100# cotton seed hulls, 8 5/8" wiper plug & 100 sax cement, use 60/40 Poz mix + 6% gel.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?       

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (316) 886-5606

ADDRESS P.O. Box 168 City/State Medicine Lodge, KS

PLUGGING CONTRACTOR Clarke Well Service KCC LICENSE # 5505 5/96  
(company name) (contractor's)

ADDRESS Medicine Lodge, KS PHONE # ( ) 316-886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)       

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/17/96 AUTHORIZED OPERATOR/AGENT: Carl W. Durr  
(signature)

KANSAS RECEIVED  
CORP CO  
MAY 23 11:52 AM '96  
5-23-96



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

May 23, 1996

Woolsey Petroleum Corporation  
107 N Market  
Wichita KS 67202

Z-Bar E #1  
API 15-007-21,092-0000  
330 FNL 2210 FWL  
Sec. 09-35S-15W  
Barber County

Dear Carl W. Durr,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,  


David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760