

RECEIVED

JUL 22 2005

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1

September 2003

This Form must be Typed

Form must be Signed

All blanks must be Filled

API # 15 - 095-01153 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7/15/1963

Well Operator: Merit Energy Company KCC License #: 32446

Address: 13727 Noel Road, Ste. 500 City: Dallas

State: Texas Zip Code: 75240 Contact Phone: (972) 628 - 1659

Lease: West Spivey Unit (TJADEN A #7) Well #: 2 Sec. 24 Twp. 30 S. R. 08 East West

NW/4SE/4 - SW - SE - NW Spot Location / QQQQ County: Kingman

2310 2904 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 3802 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 192' Cemented with: 250 Sacks

Production Casing Size: 5-1/2" Set at: 4431' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4290-98' (4/11/1966), 4270-90' (1/22/1981)

Elevation: 1599' (G.L. / K.B.) T.D.: 4420' PBDT: 4395' Anhydrite Depth: 1150', 3200'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See attached P&A procedures.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jay Iverson

Merit Energy Company Phone: (972) 628 - 1662

Address: 13727 Noel Road, Ste. 500 City / State: Dallas, TX

Plugging Contractor: TBD - will be KCC approved KCC License #: _____
(Company Name) (Contractor's)

Address: _____ Phone: () - _____

Proposed Date and Hour of Plugging (if known?): August 2005, depending on rig availability

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 07/14/2005 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**P&A Procedure
WSU 2 (Tjaden A 7)
15-095-01153
Sec. 24 T30S R08W
Kingman County, KS**

Objective: Plug and Abandon well due to loss of production and holes in casing.

Well Data:

K.B. - 1,589'

D.F. - 1,585'

G.L. - 1,578'

Tubing - Pulled out of hole

Casing - 5 1/2", 14 #, J-55 @ 4,418'. TOC @ +/- 3,348'.

Open Perf'd Interval - 4,270 - 4,298' Mississippi Chat

Procedure:

1. MIRU P&A rig.
2. Set CIPB @ 4,220' (no deeper).
3. Dump 2 SX CMT on CIPB.
4. Stretch Test 5 1/2" CSG. Shoot 5 1/2" CSG at free point and POOH laying down.
5. Set 35 SX plugs 50' below and 50' above Salt Section.
 - For depth of Salt Section, call District 2 office at (316) 630-4000
6. Circulate CMT up 8 5/8" CSG from 253' to surface.
7. RDMO P&A rig.
8. Cap well as necessary.

**RECEIVED
JUL 22 2005
KCC WICHITA**

MERIT ENERGY COMPANY

CURRENT WELLBORE

LEASE & WELL NO. WSU 2 FORMER NAME TJADEN A 7
FIELD NAME SPIVEY-GRABS COUNTY & STATE KINGMAN, KS
LOCATION SEC. 24, T30S, R08W API NO. 15-095-01153

K.B. ELEV. 1589'
D.F. ELEV. 1585'
G.L. ELEV. 1578'

OTHER FORMATION TOPS

SURFACE CASING

SIZE 8 5/8" WEIGHT 29.# DEPTH 203'
GRADE _____ SX. CMT. 250 sx CMT @ SURF

WELL HISTORY

1/7/55 COMPLETED IN MISSISSIPPI CHAT (4290 - 298')
- ACIDIZED w/ 500 GALS.
- FRAC'D w/ 8000 LBS SAND
9/12/69 FRAC'D w/ 50000 LBS SAND
1/25/81 COMPLETED IN MISSISSIPPI CHAT (4270 - 290')
- ACIDIZED w/ 500 GALS. 15% ACID
- FRAC'D w/ 50000 LBS 10/20 SAND

TUBING

PULLED OUT OF HOLE

MISSISSIPPI CHAT
4270 - 298'

LONGSTRING

SIZE 5 1/2" WEIGHT 14.# DEPTH 4418'
GRADE J-55 SX. CMT. 200 sx TOC 3348'

PBTD@ 4396'
TD@ 4420'

RECOMMENDATION

RECEIVED
JUL 22 2005
KCC WICHITA