

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 017-20019-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: Glacier Petroleum, Inc. KCC License #: 5721

Address: P.O. Box 577 City: Emporia

State: Kansas Zip Code: 66801 Contact Phone: (620) 342 - 1148

Lease: Browning Well #: 2 OWWO Sec. 24 Twp. 22 S. R. 9 East West

NW - SE - NE - _____ Spot Location / QQQQ County: Chase

3630 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 203 Cemented with: 100 Sacks

Production Casing Size: 5 1/2" Set at: 2500 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2442 to 2448

Elevation: 1589 (G.L. / K.B.) T.D.: 2555 PBDT: 2500 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Cement plug 2442 to 2392, Cement plug 250 to 150, Cement plug 60 to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? unknown

RECEIVED
FEB 15 2006
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Glacier Petroleum, Inc.

Mark Lynch Phone: (620) 344 - 1467

Address: P.O. Box 577 City / State: Emporia, KS 66801-0577

Plugging Contractor: Glacier Well Service KCC License #: 5721

Address: P.O. Box 577, Emporia, KS 66801-0577 Phone: (620) 342 - 1148

Proposed Date and Hour of Plugging (if known?): 02/27/2006

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 02/14/2006 Authorized Operator / Agent: _____ (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

E.W. SAUDER
P.O. BOX 731

#2 BROWNING 'OWHO'

24-22-9E
NW SE NE

EMPORIA, KS. 66801

CONTR FRANKLIN D. GAINES

CTY CHASE

GEOL

FIELD BROWNING



ELV 1589 KB SPD E12/18/84 CARD 7/25/85

ISSUED

F 400 MCFGPD

CHER (CATT SD) 2442-2448
(NEW PAY)

APL 15-017-20,019-A

	Top	Depth/Datum
SMP		
BKC	2034	445
ALT	2143	554
PAWN	2171	582
FT SC	2238	649
CHER	2292	703
CATT SD	2435	846
B/CATT SD	2450	861
U BY SD	2488	897
B/U BY SD	2494	905
L BY SD	2498	909
RTD	2555	988
NO LOG		

OLD INFO: OPERATOR WAS SAUDER-MURPHY-SAUDER, #2 BROWNING, SPD 7/16/72, SET 8 5/8" 203 / 100SX, COMP AS D&A/CHER 7/25/72 (CARD ISSUED 8/17/72), CONTR: JACKMAN & JACKMAN, GEOL: DEAN-SEEGER

NO DSTS

NEW INFO: FR 12/19/84, RE-ENTERED E 12/18/84, WSH DWN, SET 5 1/2" 2500, MICT - CO, PF (CATT SD) 2442-48, AC 250G (15%) & 15G (FOAM & NITROGEN), FRAC 10,000# SD & FL, SWB DWN - GSG, SI, F 400 MCFGPD, NW, 4/15/85

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

RECEIVED
FEB 15 2006
KCC WICHITA



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Glacier Petroleum Co., Inc.
825 Commercial Street
PO Box 577
Emporia, KS 66801

February 17, 2006

Re: BROWNING OWWO #2
API 15-017-20019-00-01
NWSENE 24-22S-9E, 3630 FSL 990 FEL
CHASE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely


David P. Williams
Production Supervisor