

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API # 15-065-02807-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR John J. Darrah, Jr. KCC LICENSE # 5088

ADDRESS 225 N. Market #300 (owner/company name) CITY Wichita (operator's)

STATE KS ZIP CODE 67202 CONTACT PHONE # (316)263-2243

LEASE Brush Creek Unit WELL# 204 SEC. 9 T. 9 R. 23W (East/West)

SE. SE. NW. SPOT LOCATION/0000 COUNTY Graham

2943 2790 FEET (in exact footage) FROM Q/N (circle one) LINE OF SECTION (NOT Lease Line)

3138 2970 FEET (in exact footage) FROM Q/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE none SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 212 CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3910 CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3730-3887

ELEVATION 2970KB T.D. 3901 PBDT 3901 ANHYDRITE DEPTH 2013
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE
Has been squeezed at 2359 and 3005

PROPOSED METHOD OF PLUGGING Pump gel to fill to 2000', 10 sacks down tubing. Pull tubing, to 2000',

Pump 20 sx plug w/ gel. Pull tubing. Perf of part casing at T/Dakota, Pump 20 sk plug w/ gel, fill to B/ 8 5/8,

pump 20 sk plug, if 5 1/2 in hole fill annulus to 300 psi, Top off.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? ?

If not explain why? OLD WELL

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

George Stoepfelwerth PHONE# (316) 263-2243

ADDRESS ABOVE City/State _____

PLUGGING CONTRACTOR Determined by availability KCC LICENSE # _____
(company name) (contractor's)

ADDRESS _____ PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) July 15-20

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: July 8, 2005 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

RECEIVED
JUL 11 2005
KCC WICHITA

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Beiker "A" No. 4
SE SE NW Sec. 9-9S-23W
Graham County, Kansas

Total Depth: 3910'

Elevation: 2379' RB
Production: 175 BOPD, plus 10%Wtr

Commenced: 10-5-57 Completed:

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 212' with 175 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Clay	213'		<u>TOPS</u>	
Shale & Sand	380'			
Shale & Shells	1340'	Anhydrite	2016'	(-363)
Shale & Sand	1500'	Heebner	3662'	(-1283)
Dakota Sand	1760'	Toronto	3683'	(-1304)
Shale & Red Bed	2016'	Lansing	3698'	(-1319)
Anhydrite	2052'	Total Depth	3910'	(-1531)
Shale & Shells	2070'			
Shale	2270'			
Shale & Shells	2620'			
Shale & Lime	3605'			
Lime	3910'			
Total Depth	3910'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L Bacon
Vice-President

Subscribed and sworn to before me this 21st day of October, 1957.

My Commission Expires:

December 19, 1960

Luetta M. Duncan
Notary Public

RECEIVED

JUL 11 2005

KCC WICHITA