

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
MAR 14 2005
KCC WICHITA

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-22,978-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F.G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)
ADDRESS 9431 E. Central, St 100 CITY Wichita

STATE Kansas ZIP CODE 67206 CONTACT PHONE # (316) 684-8481

LEASE KLEEPER SE WELL# 6-17 SEC. 17 T. 21E R. 11 (East/West)
KCC-3-16-05-51CA-Per RBPM5 + Scout Card.
- SW - NE - SE SPOT LOCATION/0000 COUNTY Stafford

1663 1680 FEET (in exact footage) FROM (S/N) (circle one) LINE OF SECTION (NOT Lease Line)
476 380 FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 270' CEMENTED WITH 175sx SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3660' CEMENTED WITH 150sx SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3532' - 3538' Simpson

ELEVATION 1816'KB T.D. 3670' PFTD N/A ANHYDRITE DEPTH 542'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, hulls, cement and plug according to KCC regulations.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long

PHONE# (620) 793-0915/(620) 786-5783

ADDRESS P.O. Box 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service KCC LICENSE # 31925

ADDRESS 401 West Main, Lyson, KS. 67554 (company name) (contractor's)
PHONE # (620) 727-3410

PROPOSED DATE AND HOUR OF PLUGGING (If known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 03/11/2005 AUTHORIZED OPERATOR/AGENT: Louveness Mpanje
(signature)

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

COPY

SAMPLE LOG ----- KLEPPER SE #6

Located: 1650' FNL & 330' FWL SE/4 Sec. 17-22S-11W,
Stafford County, Kansas

OWNER: BILL CHEW, INC.

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: November 4, 1994

COMPLETED: November 9, 1994

TOTAL DEPTH: 3670' Driller
3669' Logger

LOG

0' - 100' Sand
100' - 275' Red Bed
275' - 870' Red Bed and Shales
870' - 1600' Shale
1600' - 3478' Shale and Lime
3478' - 3575' Lime, Shale and Sand
3575' - 3670' Lime and Shale

CASING RECORD

Spud at 11:30 AM, 11-04-94. Ran 6 joints 8 5/8" new 20# surface casing. 258.47' set at 270' K.B. Cemented with 175 sacks of 60/40 Poz mix with 2% gel, 3% cc. Plug down at 4:45 PM 11-04-94 by Allied ticket #1145. Good returns.

Ran 107 joints of 5 1/2" 14# used casing. 3649.72' pipe set at 3660' K.B. Cemented with 150 sacks 60/40 Pozmix with 500 gal. Superflush and 20 BBL of salt flush ahead of cement. Plug down at 1:30 AM 11-09-94. Centralizers on 1-2-4-6-8 and 10th joint. Plugged rathole with 15 sacks.

DEVIATION SURVEY

3/4° @ 275'

1/2° @ 3670'

RECEIVED

MAR 14 2005

KCC WICHITA