

1 010107

API NUMBER 15- 007-20,549A-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 11, T 35 S, R 12 W/E

3300 feet from S section line

3300 feet from E section line

Lease Name Kessler Well # 1

County Barber 171.93

Well Total Depth 5290 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1033

TECHNICIAN'S PLUGGING REPORT

Operator License # 5188

Operator: Silver Creek Oil & Gas

Name &

Address 1900 N. Adam

Wichita, KS 67203

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 am Day: 10 Month: March Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 5268' PBD 5214' Perfs at 4814-24'

1st plug sand back to 4765' and dump 4sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:50 am Day: 10 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4765' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 600 psi and shut in 400 psi

Remarks: Recovered 4050' 4 1/2" casing. Used 60/40 Pozmix 2% cc by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed

Paul A. Luthi (TECHNICIAN)

DATE MAR 20 1986

3-20-86 MAR 20 1986

INV. NO. 13054