

15-09-21333-0000

To: 1 010097
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 12-18-81
N/2 NE SE, SEC. 10, T. 35 S, R. 12 W/E
2310 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5188
Operator: Silver Creek Oil & Gas
Name & Address: 1400 N. Amidon
Wichita, KS 67203

Lease Name Kessler Well # 3
County Barber
Well Total Depth 5320 172.90 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P. O. Box 197, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:45 pm Day: 25 Month: February Year: 19 86

Plugging proposal received from Elmo Morgenstern
(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 5357' PBT 5314' Never Perforated
Shoe joint never drilled out
Squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 pm Day: 25 Month: February Year: 19 86

ACTUAL PLUGGING REPORT Squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, and 125 sx cement

Maximum pressure 400 psi and shut in 200 psi

Remarks: Recovered 4650' 4 1/2" casing. Used 60/40 Pozmix 2% cc by Allied.
(If additional description is necessary, use BACK of this form.)

I, (did / ~~did not~~) observe this plugging.
DATE MAR 12 1986
Signed Jack P. Butler (TECHNICIAN)

INV. NO. 12963
2-25

MAR 11 1986
3-11-86
CONSERVATION DIVISION
Wichita, Kansas