

To: 1 120028
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Operator: *Farrar Pump & Supply

Name & Address P.O. Box 209

Medicine Lodge, KS 67104

*was Silver Creek

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☐

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 7 Month: 10 Year: 19 87

Plugging proposal received from Elmo Morganstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4924' PBSD 4885' not perforated

1st plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11 a.m. Day: 7 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped through 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 300-400 psi and shut in 200 psi.

*this well was obtained through the court. Former operator was Silver Creek

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 4360' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
If necessary, observe this plugging.

DATE 10-14-87

INV. NO. 18491

10-7-87
API NUMBER 15- 007-21,332 -0000

C NW NW, SEC. 10, T 35 S, R 12 W/E

4620 feet from S section line

4620 feet from E section line

Lease Name Kesler Well # 2

County Barber 160.06

Well Total Depth 4925 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Signed Duane Rankin (TECHNICIAN)