

1 120029

10-7-87

API NUMBER 15- 007-20,847 -0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NE NE, SEC. 10, T 35 S, R 12 W/E

4290 feet from S section line

330 feet from E section line

Lease Name Kesler Well # 1

County Barber 156.88

Well Total Depth 4827 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 317

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Operator: \*Farrar Pump & Supply

Name & Address P.O. Box 209

Medicine Lodge, KS 67104

\* was Silver Creek

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:30 a.m. Day: 7 Month: 10 Year: 19 87

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4817' Open hole 4817-27'

1st plug sand back to 4755' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 7 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4755' and dumped 4 sx cement on top of

sand through bailer,

2nd plug dumped through 10 3/4" surface casing with 300 lbs. hulls, 10 sx gel, 30 sx cement,

10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 120 sx cement.

STATE CORPORATION COMMISSION

Pumping pressure 200 psi and shut in 0 psi.

OCT 13 1987 10-13-87

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3900' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

This well was obtained through the court. Former owner - Silver Creek. (If you observe this plugging, observe this plugging.)

INVOICED

DATE 10-14-87

Signed Duane Rankin (TECHNICIAN)

INV. NO. 18492