

1040951

API NUMBER 15- 007-21,165-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION App. NE NE NE, SEC. 14, T 35 S, R 12 W/E

130 S. Market, Room 2078
Wichita, KS 67202

5005 feet from S section line

420 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31248

Lease Name Gottsch-Peter-Well / 1
mann

Operator: Duane L. Waugh dba C & D Supply

County Barber

Name & Address RR 2, Box 164

Well Total Depth 4920 159.90 feet

Cherokee, OK 73728

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 333

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 11:10 p.m. Day: 11 Month: 4 Year: 19 95

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Notes: 4 1/2" at 4920' w/150 sx cement, Tubing left in hole-top of tubing fish @ 3300'

1st plug push rubber wiper plug to 3251' and spot 25 sx cement through tubing inside of 4 1/2" casing at 3251',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:40 p.m. Day: 11 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pushed rubber wiper plug to 3251' and spotted 25 sx cement through tubing inside of 4 1/2" casing at 3251',

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, and 125 sx cement.

Maximum pressure 650 psi and shut in 400 psi.

No wiper plug-surface pipe plated.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I will observe this plugging.

DATE 4-21-95

Signed Stephen J. Durrant
(TECHNICIAN)

INV. NO. 42656

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1995
CONSERVATION DIVISION
WICHITA, KANSAS