

To: 1 052220
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

AP# NUMBER 15- 007-21,645 - 0000
NW SE NW NW, SEC. 13, T 35 S, R 12 WXX
4450 feet from S section line
4590 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006
Operator: Molz Oil Company
Name & Address: RR 2, Box 54
Kiowa, KS 67070

Lease Name Yates C Well # 1
County Barber 159.93
Well Total Depth 4921 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 253

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10 a.m. Day: 28 Month: 1 Year: 19 98

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-885-5665

were: 5 1/2" at 4920' w/100 sx cement, PBSD 4904', Perfs at 4834-64'

1st plug sand back to 4775' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 28 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 100 psi.

FEB 03 1998
2-3-98

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 5 1/2" casing. (For additional description is necessary, use BACK of this form.)

INVOICED
FEB 05 1998

DATE: (old / XXXXXX) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 50033