

1 010032

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SE SE, SEC. 13, T 35 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,061-0000
330 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5105

Lease Name AHS Cattle Well # 1

Operator: Clarke Corporation for Ward Oil Co.

County Barber 157.92

Name & Address 411 South 2nd Street

Well Total Depth 4859 feet

McAlester, OK 74503

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 804

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 am Day: 9 Month: September Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4848' Open Hole

1st plug sand back to 4800' and dump 4 sx cement on top of sand through drill pipe

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:00 am Day: 9 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of sand
through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel,
1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 550 psi and shut in 300 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. Recovered 3400' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION

SEP 17 1985

DATE

SEP 16 1985

Signed

(TECHNICIAN)

INV. NO. 10110

CONSERVATION DIVISION
Wichita, KansasFORM CP-2/3
Rev. 01-84