

010102 corrected

Doc/lat # D-22, 103

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,264-00-01

SW SW SW , SEC. 12 , T 35 S, R 12 W/E

330 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Sternberger Well # 1

Operator: Edmiston Oil Co., Inc.  
Name & Address: 1260 Kansas State Bank Building  
Wichita, KS 67202

County Barber

Well Total Depth 4895 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 313

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 pm Day: 5 Month: March Year: 19 86

Plugging proposal received from Roger Luss

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4894' PBD 4885' Perfs at 4826-4836'; 3838-3850'

1st plug sand back to 4775' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls-  
release 10 3/4" rubber plug and pump 150 sx cement

RECEIVED  
STATE CORPORATION COMMISSION

MAY 17 1989  
5-17-89  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:40 pm Day: 5 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4775' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls, released 10 3/4" rubber plug and pumped 150 sx cement.

Maximum pressure 550 psi and shut in 300 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

# Electra Log Inc.

## Radiation Log

COMPANY	RAM PETROLEUM CORPORATION		
WELL	STERNBURGER #1	JUN 29 1983	
FIELD			
COUNTY	BARBER	STATE	KANSAS
Location	SW SW SW	Other Services: STRIPS	
Sec. 12	Twp. 35S	Rge. 12W	

Permanent Datum:	GROUND LEVEL	Elev. 1370'	Elev. K.B. 1375'
Log Measured From	K. B. FIVE	Ft. Above Perm. Datum	D.F. 1372'
Drilling Measured From	KELLY BUSHING		G.L. 1370'

Date	6-21-83				
Run No.	ONE				
Depth - Driller	N. A.				
Depth - Logger	4878'				
Btm. Log Inter.	4877'				
Top Log Inter.	1500'				
Casing - Driller	@	@	@	@	@
Casing - Logger					
Bit Size					
Type Fluid in Hole	WATER OIL				
Dens.   Visc.					
pH   Fluid Loss		ml	ml	ml	
Source of Sample					
Rm @ Meas. Temp.	@	°F	@	°F	@
Rmt @ Meas. Temp.	@	°F	@	°F	@
Rmc @ Meas. Temp.	@	°F	@	°F	@
Source: Rmt Rm					
Rm @ BHT	@	F	@	°F	@
Time Since Circ.					
Max. Rec. Temp.		°F		°F	
Equip.   Location	141	GREAT BEND			
Recorded By	L. STUKEY				
Witnessed By	MR. MAY				

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1986 °F  
1-21-86  
CONSERVATION DIVISION  
WICHITA, KANSAS