

1 040901

10-28

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drilled 1955 15-007-10392-0000

C NE NE, SEC. 6, T 35 S, R 12  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Ohlson Well # 1

Operator: John O. Farmer, Inc.

County Barber

Name & Address 370 W. Wichita Ave., Box 352

Well Total Depth 4817 156.55 feet

Russell, KS 67665

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 9 5/8 feet 263

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 10 Year: 19 94

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

well: 5 1/2" at 4816' w/250 sx cement, PBSD 4810', Perfs at 4785-96'

1st plug sand back to 4730' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
9 5/8" wiper plug, and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 28 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4730' and dumped 5 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 9 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 11-7-94

INV. NO. 41585

RECEIVED STATE CORPORATION COMMISSION NOV 0 3 1994 11-3-94  
Signed \_\_\_\_\_ (TECHNICIAN)