

To: 1 080132 7-8  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- N/A 15-007-01103-0000  
C NE SW, SEC. 6, T 35 S, R 12 W/X  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5135  
Operator: John O. Farmer, Inc.  
Name  
Address P.O. Box 352  
Russell, KS 67665

Lease Name Olsen Well # A-1  
County Barber 156.49  
Well Total Depth 4815 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 9 5/8 feet 254

Abandoned Oil Well Gas Well X Input Well SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 8 Month: 7 Year: 19 97

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4814' w/250 sx cement, PBTD 4814', Perfs at 4746-68'  
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump down 9 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, and 125 sx cement.

Plugging Proposal Received by Kevin Strube  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X  
Operations Completed: Hour: 2:30 p.m. Day: 8 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4685' and dumped 5 sx cement on top of sand  
through bailer,  
2nd plug pumped down 9 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls and 125 sx cement.  
Maximum pressure 300 psi and shut in 200 psi.

RECEIVED  
JUL 16 1997  
STATE CORPORATION COMMISSION  
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify that I have observed this plugging.

Signed Kevin P. Strube  
(TECHNICIAN)

DATE JUL 16 1997  
CVL NO. 48543