

To: 040676 7-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,865-0000 228 R
NE NW NE, SEC. 4, T. 35 S, R 12 W/R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Operator: Gore Oil Company
Name & Address P.O. Box 2757
Wichita, KS 67201-2757

4950 feet from S section line

1650 feet from E section line

Lease Name Graves A Well # 3

County Barber 158.27

Well Total Depth 4870 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30 a.m. Day: 29 Month: 7 Year: 19 92

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4870' w/275 sx cement, PBTD 4859', Perfs at 4800-4808'

1st plug sand back to 4750' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 29 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10

sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3350' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(and, if possible, observe this plugging.)

DATE 8-10-92

INV. NO. 35912

Signed Steve Pfeifer
(TECHNICIAN)