

1 040434

6-29

API NUMBER 15- 007-20,958 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE NE, SEC. 4, T 35 S, R 12 W/E

4950 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3906

Lease Name Vogel Well # 3

Operator: Robert McCandless

County Barber 158.54

Name & Address 719 Illinois

Well Total Depth 4878 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 412

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:30 p.m. Day: 29 Month: 6 Year: 19 90

Plugging proposal received from Robert McCandless

(company name) Robert McCandless (phone) 316-672-6681

were: 4 1/2" at 4874' Perfs at 4810-20'

1st plug sand back to 4760' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls, and 150 sx

cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 29 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4760' and dumped 4 sx cement on top

of sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 200 lbs. hulls and 150 sx cement.

Maximum pressure 300 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3500' of 4 1/2" casing

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 7-9-90

INV. NO. 28553

RECEIVED STATE CORPORATION COMMISSION

JUL 6 1990 7-6-90

CONSERVATION DIVISION Wichita, Kansas