

9-20

79 R

1 040321

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21.704-0000  
NW NW NW, SEC. 2, T 35 S, R 12 W E  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086  
Operator: Pintail Petroleum, Ltd.  
Name & Address 412 East Douglas, Suite One  
Wichita, KS 67202

Lease Name Frieden A Well # 4  
County Barber 157.95  
Well Total Depth 4860 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 763

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:15 p.m. Day: 20 Month: 9 Year: 1989

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711  
were: 4 1/2" at 4859' Open hole from 4859-60'

1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 100 lbs. hulls, release 8 5/8"  
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of  
sand bridge with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 22 1989  
9-22-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2912' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-28-89

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INV. NO. 25975