

1 040326

9-29

1910

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,850 - 0000

NE NW SW, SEC. 2, T 35 S, R 12 W/E

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Frieden "A" Well # 3

Operator: Pintail Petroleum, Ltd.

County Barber 156.94

Name & Address 412 East Douglas, Suite One

Well Total Depth 4829 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 281

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 29 Month: 9 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4810' Open hole at 4810-29'

1st plug sand back to 4760' and dump 4 sx cement on top of sand bridge with bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:45 p.m. Day: 29 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4760' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

6 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

RECEIVED STATE CORPORATION COMMISSION

OCT 05 1989 10-5-89

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2109 INCHES 1/4" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(operator) observe this plugging.

DATE 10-9-89

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 26057