

1 040327

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-29 15-007-20307-00-01179 R
API NUMBER 15- Docket #E-21,428
200' SE of
C E/2 E/2 SEC. 2, T 35 S, R 12 W/E

2630 feet from S section line
450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Frieden "A" Well # 1

Operator: Pintail Petroleum, Ltd.
Name &
Address 412 East Douglas, Suite One
Wichita, KS 67202

County Barber 168.35
Well Total Depth 5180 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 228

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 9 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 5170' PBD 5126' Perfs at 4848-54'

1st plug sand back to 4800' and dump 4 sx cement on top of sand bridge with bailer,
2nd plug pump 80 sx ATL cement down 4 1/2" casing,
3rd plug pump 50 sx cement down 10 3/4" X 4 1/2" annulus.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 29 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of
sand bridge with bailer,

Shot pipe at 1824', couldn't pull, shot pipe at 641' to squeeze,
2nd plug pumped down 4 1/2" casing with 80 sx ATL cement, Maximum pressure 200 and shut in
50 psi,

10-5-89
RECEIVED
OCT 05 1989

3rd plug pumped down 10 3/4" X 4 1/2" annulus with 50 sx 60/40 Pozmix 6% gel, Maximum pressure
100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel and ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-9-89
INV. NO. 26055

Signed Stephen J. Pfeifer
(TECHNICIAN)