

1030270

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,060-0000

NE NW SE , SEC. 9 , T 35 S, R 12 W/E  
N SE Corner of  
2310 feet from ~~NXS~~ section line  
W SE Corner of  
1650 feet from ~~NXE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name Achenbach Well # 1

Operator: G. N. Rupe - Etal.  
Name &  
Address P. O. Box 2273  
Wichita, KS 67202

County Barber  
Well Total Depth 4939 160.52 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 7 Month: September Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 4938' PBD 4897' Perfs 4862'

1st plug sand back to 4810' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement

Plugging Proposal Received by Steve Dumont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00 am Day: 7 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4938' PBD 4897' Perf 4862'

1st plug sanded back to 4810' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement.

100 sx cement.

Shut in pressure 500 psi

RECEIVED  
STATE CORPORATION COMMISSION  
9-17-84  
SEP 17 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

Signed Steve Dumont  
(TECHNICIAN)

DATE \_\_\_\_\_  
INV. NO. 3799