

2-7 15-007-20944-0000

To: 1 040224
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 7/29/80

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corporation
Name & Address: Box 723
Hays, KS 67601

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1989

2-13-89
CONSERVATION DIVISION
Wichita Kansas

990 feet from S section line

1980 feet from E section line

Lease Name L.J. Well # 1

County Barber 158.57

Well Total Depth 4879 feet

Conductor Pipe: Size 16 feet 105

Surface Casing: Size 8 5/8 feet 417

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 6105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 7 Month: 2 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4878' Perfs at 4870-77'

1st plug sand back to 4820' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 7 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4820' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 3500' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 2-17-89

INV. NO. 23955

Signed Stephen J. Pfeifer (TECHNICIAN)