

1 040410

4-4

76

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,030-0000
SE NW NW, SEC. 8, T 35 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

4290 feet from S section line

4290 feet from E section line

Operator: Edmiston Oil Company, Inc.

Lease Name Ohlson "B" Well # 4

Name & Address 1260 KSB Building

County Barber 158.70

Wichita, KS 67202

Well Total Depth 4883 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 340

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS

Company to plug at: Hour: 11:30 a.m. Day: 4 Month: 4 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4879' Perfs at 4796-4806'

1st plug sand back to 4750' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 175 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 4 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 175 sx cement.

Maximum pressure 350 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3340' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-24-90

INV. NO. 27935

RECEIVED
APR 11 1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Stephen J. Pfeiffer
(TECHNICIAN)