

To: 1 041216
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 007-21,155-0000

NW NE SE, SEC. 8, T 35 S, R 12 W/EX
2310 feet from S section line
990 feet from E section line

Operator License # 5364
Operator: Beren Corp.
Name & Address: P.O. Box 723
Hays, KS 67601

Lease Name McNally Well # 1
County Barber 158.86
Well Total Depth 4888 feet
Conductor Pipe: Size 16" feet 105
Surface Casing: Size 8 5/8" feet 408

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 24 Month: 10 Year: 19 96

Plugging proposal received from Jeff Clarke
(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 4878' with 250 sx cement, Perfs at 4863-70'
1st plug sand back to 4760' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 24 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4760' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-31-96

INV. NO. 46887

10-24

Signed Stephen J. Pfeifer
(TECHNICIAN)