

1080549

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,216-0000

NW NE NW, SEC. 17, T 34 S, R 12 W/E

4950 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5188

Lease Name Reynolds-Mikit # 1

Operator: Silver Creek Oil & Gas
Name & Address: 1900 N. Amidon, Suite 221
Wichita, KS 67203

County Barber

160.88

Well Total Depth 4950 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 18 Month: 9 Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corp. (phone) 316-886-5665

were: 4 1/2" at 4942 PBTD 4896 Perfs at 4844-4848

1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls and 110 sx Econolight or Thrifty mix

Plugging Proposal Received by Don Ubel

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 2 p.m. Day: 18 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back from 4996 to 4800 and dumped 4 sx cement
on top of sand through bailer

2nd plug squeezed well with 3 sx hulls and 110 sx cement

Maximum pressure 350 and shut in at 250 psi

Remarks: Recovered 3550' 4 1/2" casing. Used thrifty mix by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-23-86

INV. NO. 15006

9-18

SEP 23 1986
9-23-86

Signed

J. A. Titan
(TECHNICIAN)

GREAT GUNS

Correlation Log

LE NO.	COMPANY <u>SILVER CREEK MANAGEMENT</u>			
	WELL <u>NO. 1 REYNOLDS - MIKITA</u>			
	FIELD _____			
	COUNTY <u>WABER</u>		STATE <u>KANSAS</u>	
	LOCATION:		OTHER SERVICES	
	<u>N.E. 4 NE. 4 N. 14</u> <u>34</u> <u>SEC 17 TWP 35 S RGE 12 W</u>			
Permanent Datum	<u>G.L.</u>	Elev. <u>1405</u>	Elevations:	
Measured from	<u>K.B.</u>	<u>5</u> Ft. Above Permanent Datum	KB <u>1410</u>	
Log Measured from	<u>K.B.</u>		DP _____	
			GL <u>1405</u>	
No.	<u>8-5-81</u>			
Driller	<u>ONE</u>			
Logger	<u>4950</u>			
Logged Interval	<u>4896</u>			
Logged Interval	<u>4796</u>			
Driller	<u>2</u>	<u>2</u>	<u>2</u>	<u>2</u>
Logger				
Flow				
Fluid in Hole				
Quantity and Viscosity				
and Fluid Loss				
Core of Sample				
1st Meas. Temp.	<u>2</u>	<u>1P</u>	<u>2</u>	<u>1P</u>
2nd Meas. Temp.	<u>2</u>	<u>1P</u>	<u>2</u>	<u>1P</u>
3rd Meas. Temp.	<u>2</u>	<u>1P</u>	<u>2</u>	<u>1P</u>
Core of Ref. and Rec.				
1st GHT	<u>2</u>	<u>1P</u>	<u>2</u>	<u>1P</u>
2nd GHT				
3rd GHT				
1st Sec. Temp. Dev. P		<u>1P</u>		<u>1P</u>
2nd Sec. Temp. Dev. P				
3rd Sec. Temp. Dev. P				
1st No. and Location				
2nd No. and Location				
3rd No. and Location				
1st By	<u>REARDON</u>			
2nd By	<u>MC KEEN</u>			

4700

