

15-007-19105-0000

To: 1010085  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 8-22-38

W/2 SW, SEC. 14, T 33 S, R 13 W/EX

1320 feet from S section line

4620 feet from E section line

Lease Name Angell "C" Well # 3

County Barber 161.85

Well Total Depth 4980 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 280

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Operator: Chevron U.S.A., Inc.

Name & Address P. O. Box 12116

Oklahoma City, OK 73157

ATTN: D. Y. Mitchell

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Chevron U.S.A., Inc. License Number 4519

Address P. O. Box 12116, Oklahoma City, OK 73157

Company to plug at: Hour: 10:15 am Day: 31 Month: January Year: 19 86

Plugging proposal received from Dan Massingill

(company name) Chevron (phone) 405-949-7000

were: 7" at 4802' PBTD 4700' Perfs at 4515-70'

1st plug pump 90 sx gel and 110 sx cement to bottom (common cement).

Pull tubing and shoot 4 holes at 243'

2nd plug run 900' of tubing and pump 175 sx cement (common cement). to circulate

Pull tubing and tie back onto 7".

3rd plug pump 100 sx cement (common 2% cc cement)

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:25 pm Day: 31 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 90 sx gel and 110 sx cement on bottom. Pulled tubing

and shot 4 holes at 243'. 2nd plug ran 900' of tubing and pumped 175 sx cement. Cement

circulated. Pulled tubing and tied back onto the 7". 3rd plug pumped 100 sx cement.

Cement came to surface between the 7" and the 10 3/4".

Took 300 lbs to pump the last 100 sx cement.

2-1-86 - cement fell to 70' -- filled with common cement.

Remarks: No recovery. Used common cement 2% cc by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED  
FEB 11 1986

DATE \_\_\_\_\_

INV. NO. 12509

RECEIVED  
STATE CORPORATION COMMISSION

FEB 10 1986

2-10-86  
CONSERVATION DIVISION  
Wichita, Kansas

John D. Gault  
(TECHNICIAN)