

1 080526

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,869 - 0000

C E/2 NE SW, SEC. 7, T 35 S, R 12 W/W

1980 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Haskard "D" Well # 4

Operator: Edmiston Oil Co., Inc.
Name & Address: 1260 Kansas State Bank Building
Wichita, KS 67202

County Barber 158.76

Well Total Depth 4885 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:10 pm Day: 14 Month: May Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4884' PBD 4875' Perfs at 4832-4842'

1st plug pump 25 sx cement to bottom with 1 sack hulls

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 110 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:05 pm Day: 14 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom and stopped

plug at 4700'. Maximum pressure 700 psi and shut in 300 psi. 2nd plug squeezed well

with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber

plug and pumped 110 sx cement.

Maximum pressure 500 psi and shut in 100 psi

Remarks: Recovered 3400' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
MAY 27 1986
5-27-86
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Observe this plugging.

DATE MAY 27 1986

Signed _____
(TECHNICIAN)

INV. NO. 13973