

3-15-88

1 040068

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,721-0000
NE SE, SEC. 7, T 35 S, R 12 W EX
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042
Operator: Edmiston Oil Company, Inc.
Name & Address 1260 Kansas State Bank Bldg.
Wichita, KS 67202

Lease Name Haskard "D" Well # 1
County Barber 158.37
Well Total Depth 4873 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 15 Month: 3 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4872' PBSD 4872' Perfs at 4802-08, 4812-21'
1st plug sand back to 4760' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:45 p.m. Day: 15 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3302' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
3-23-88
MAR 23 1988

INVOICED
I will / ~~will not~~ observe this plugging.

DATE 3-25-88
INV. NO. 20186

Signed Stephen J. Pfeifer
(TECHNICIAN)