

3-30-88

1 040077

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,674-0000
SW NE, SEC. 7, T 35 S, R 12 W 2E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Haskard "C" Well # 1

Operator: Edmiston Oil Company, Inc.

County Barber 158.54

Name & Address 1260 Kansas State Bank Bldg.

Well Total Depth 4878 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 30 Month: 3 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4876' PBD 4876' Perfs at 4812-22'

1st plug sand back to 4760' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 30 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4760' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1988
4-11-88

Maximum pressure 400 psi and shut in 250 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2624' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

(and observe this plugging.)

DATE 4-13-88

Signed Stephen J. Pfifer
(TECHNICIAN)

INV. NO. 20342