

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20426-00-01
Spot: NENWSW Sec/Twnshp/Rge: 4-35S-14W
2310 feet from S Section Line, 990 feet from W Section Line
Lease/Unit Name: BENSON Well Number: 2-4
County: BARBER Total Vertical Depth: 4883 feet

Operator License No.: 3080
Op Name: JACK EXPLORATION, INC.
Address: PO BOX 1279 812 W. 11TH STREET
SULPHUR, OK 73086

Conductor Pipe: Size feet: 8/58.70
Surface Casing: Size 8.625 feet: 791
Production: Size 4.5 feet: 4882 TOP CEMENT 3850
Liner: Size feet:

Well Type: QG UIC Docket No: Date/Time to Plug: 06/19/2002 12:45 PM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: ALAN WATSON Company: JACK EXPLORATION Phone: (580) 612-3679

Proposed Plugging Method: CIBP @ 4500' & 2 SX CMT. 1ST PLUG AT 820' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER
Date/Time Plugging Completed: 06/19/2002 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4650'. PERFS AT 4594-4604'. SET CIBP @ 4500' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 820' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

JUN 24 2002
6-24-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3650' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED JUN 20 2002
DATE 6-24-02
INV. NO. 2002062005