

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22682-00-00
Spot: SWSW Sec/Twnshp/Rge: 3-35S-14W
660 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: BENSON Well Number: 1-3
County: BARBER Total Vertical Depth: 4975 feet

Operator License No.: 3080
Op Name: JACK EXPLORATION, INC.
Address: PO BOX 1279 812 W. 11TH STREET
SULPHUR, OK 73086

Production Casing Size: 4.5 feet: 4934 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 293 WITH 300 SX CMT

\$161.69

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/09/2003 1:00 PM
Plug Co. License No.: 33062 Plug Co. Name: R & R WELL SERVICE, INC.
Proposal Rcvd. from: ALAN WATSON Company: JACK EXPLORATION Phone: (580) 621-3679

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/09/2003 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4954'. PERFS AT 4892-4910, 4832-4882, 4650-4658'. SET CIBP @ 4605' & PUT 2 SX CMT ON TOP OF BRIDGE PLUG THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. PULLED OUT OF HOLE AND TOPPED OFF WITH 15 SX CMT.

RECEIVED
4-14-03
APR 14 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-15-03

INV. NO. 2003061413