

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-30333-00-00
Spot: S2 Sec/Twnshp/Rge: 9-35S-14W
1470 feet from S Section Line, 2640 feet from E Section Line
Lease/Unit Name: WOLGAMOTT Well Number: 1
County: BARBER Total Vertical Depth: 4900 feet

Operator License No.: 3532
Operator Name: CMX, INC.
Address: 1026 UNION CENTER BUILDING
WICHITA, KS 67202

Conductor Pipe: Size 13 feet: 40
Surface Casing: Size 8.625 feet: 368
Production: Size 4.5 feet: 4900
Liner: Size feet: 159.25

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2000 10:45:00 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: _____ Company: _____ Phone: (316) 886-5665

Proposed Plugging Method: PUMP 200# HULLS & 20 SXS OF COMMON CEMENT, DISPLACE TO 4700' PERFORATE @ 600' PUMP DOWN 4 1/2 WITH 175 SXS CEMENT CIRCULATING UP 8 5/8 USING 60/40 POZMIX 6% GEL.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/14/2000 12:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4830. PERFS AT 4800-06, 4808-15. SQUEEZED AT 2496' WITH 200 SX CMT. CIBP @ 3025'. PERFORATE AT 600'. BROKE CIRCULATION. PUMPED 200 SX CMT. CEMENT CIRCULATED UP 4 1/2/ 8 5/8 ANNULUS. SHUT IN PRESSURE 75#. MAXIMUM PRESSURE 150#.

STATE CORPORATION COMMISSION
SEP 18 2000
7-18-00
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed _____ (TECHNICIAN)

INVOICED
DATE 9/25/00
WELL NO. 2001060746

Form CP-2/3
SEP 15 2000
MP

DRILLER'S LOG

COMPANY: Shenandoah Oil Corporation
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: CHARLES WOLGANOTT #1
 LOCATION: 150' NE of C 3 1/2 SEC. 9-35S-14W
 BARBER COUNTY, KANSAS
 COMMENCED: 5-29-67
 COMPLETED: 6-13-67

0	20	Sand
20	1030	Redbed
1030	1487	Shale, Shells
1487	1497	Anhydrite
1497	1835	Shale, Shells
1835	2635	Lime
2635	2790	Lime, Shale
2790	2990	Lime
2990	4121	Lime, Shale
4121	4848	Lime
4848	4900	Cherty Lime
	<u>4900</u>	<u>RTD - Set 4 1/2" Casing</u>

Set 2 joints of 13 3/8" new conductor casing . 40.10' cemented with 100 sacks Common, 4% cc plus set 9 joints of new 8 5/8" surface casing @ 368.45' cemented with 300 sacks Common, 2% cc and cement did not circulate so cemented through 1" . 48' with 50 sacks Common, 3% cc; used rector guide shoe and Baker centralizer @ 328' and 47'

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wolgamott #1 Well, located 150' Northeast of Center of South Half (150' NE of C 3 1/2) of Section 9, Township 35 South, Range 14 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 14th day of June, 1967.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971

15-007-30333-0000

4600

B/Kansas City

4700

Cherokee

NOV 07 1977
11-7-77
CORPENTON DISTRICT
MICHAEL KELLER

4800
8'
8'-15'

MISS.

CTBP

