

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22680-00-00
Spot: NESE Sec/Twnshp/Rge: 9-35S-14W
1980 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: WOLGAMOTT Well Number: 2-9
County: BARBER Total Vertical Depth: 5000 feet

Operator License No.: 3080
Op Name: JACK EXPLORATION, INC.
Address: PO BOX 1279 812 W. 11TH STREET
SULPHUR, OK 73086

Production Casing Size: 4.5 feet: 5000 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 284 WITH 200 SX CMT
3162.50

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/05/2003 8:00 AM
Plug Co. License No.: 33062 Plug Co. Name: R & R WELL SERVICE, INC.
Proposal Rcvd. from: ALAN WATSON Company: JACK EXPLORATION Phone: (580) 571-7609

Proposed Plugging Method: CIBP @ 4750' & 2 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 315' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/05/2003 9:00 AM KCC Agent: STEVE PFEIFER


Actual Plugging Report:

PBTD 4970'. PERFS AT 4792-4805, 4825-4844, 4876-4898'. SET CIBP @ 4750' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3197' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
RECEIVED (TECHNICIAN)

FEB 13 2003

KCC WICHITA

INVOICED

INV. NO. 2003061204

Form CP-2B