

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19129-00-01  
Spot: SWSWSW Sec/Twnshp/Rge: 19-8S-17W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: H A KRUG Well #: 7  
County: ROOKS Total Vertical Depth: 3414 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3403		150 SX
SURF	8.625	1310		660 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2014 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP Phone: (785) 885-8240

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 15 sx gel spacer and 600 # hulls.  
Production perforations: 3126' - 3414'

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2014 11:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1300'. Ran tubing to 3286' and pumped 11 s gel spacer followed by 75 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 200 sx cement w/150 # hulls. Pulled tubing to 800' and pumped 175 sx cement. Ran out of cement. Operator decided to pull all tubing out of hole and run back in the next morning to tag cement and finish plug.  
02/18/14-Ran tubing back in hole. Tagged top of cement at 960'. Pulled up to 935' and pumped 70 sx cement w/150 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/10 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 300 psi.

GPS: 39.33644N -099.26820W

Perfs:

Top	Bot	Thru	Comments
3202	3345		

Remarks: ALLIED

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

✓ 3/24/14

MAR 03 2014

KCC WICHITA

Form CP-2/3

MAR 05 2014

RECEIVED