

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40136-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 21-26S-5E
2983 feet from S Section Line, 4957 feet from E Section Line
Lease Name: KOOGLER Well #: 65
County: BUTLER Total Vertical Depth: 2534 feet

Operator License No.: 5030

Op Name: VESS OIL CORPORATION

Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2484		
PROD	7	2467		0 SX
SURF	15.5	18		
SURF	8.625	2131		0 SX

Well Type: EOR

UIC Docket No: E03016.2

Date/Time to Plug: 02/12/2014 8:00 AM

Plug Co. License No.: 32991

Plug Co. Name: SIMMONS WELL SERVICE, INC.

Proposal Rcvd. from: CASEY COATS

Company: VESS OIL CORPORATION

Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS/ 50 SXS @ BOTTOM OF 7", 250' -0" CIRC CEMENT.

Plugging Proposal Received By: JEFF KLOCK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/12/2014 2:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

PLATED CASING STRINGS TOGETHER @ SURFACE. RIH W/TBG @ 2485'. CONSOLIDATED OIL WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS CLASS A COMMON 4% CC, 1# POLYFLAKE & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 2002'. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 250'-251' (4 HOLES). SWEDGED INTO 4 1/2" CASING, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 209 SXS CLASS A COMMON 2% CC TO SURFACE. CEMENT CIRCULATED. SHUT IN. PLUG DOWN 2-12-2014, 2:00 P.M. CONSOLIDATED CEMENT TICKET #43807.

Perfs:

Top	Bot	Thru	Comments
2467	2484	OH	

Remarks:

Plugged through: TBG

KCC WICHITA

MAR 06 2014

RECEIVED

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

cc TO UIC 3/4/14
3/24/14