

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20606-00-00
Spot: NESWNE Sec/Twnshp/Rge: 11-18S-43W
4514 feet from S Section Line, 779 feet from E Section Line
Lease Name: NORMA Well #: 3-11
County: GREELEY Total Vertical Depth: 5295 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2017		WITH 410 SX CMT
PROD	5.5	5294	0	WITH 210 SX CMT
SURF	8.625	307		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2014 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: JOE RUPP Company: VESS OIL Phone: (785) 798-5151

Proposed Plugging Method: CIBP @ 5100' WITH 2 SX CMT OR 30 SX CMT WITH 200# HULLS. PLUG AT 2700' WITH 30 SX CMT. FILL 5 1/2" WITH CMT FROM 2500' TO 0'. ATTEMPT TO PUMP INTO ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2014 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

LEFT 22 JOINTS OF 2 7/8" TBG & TBG ANCHOR IN WELL. 2/28/14: PUMP 30 SX CMT & 125# HULLS AT 4361'. FULL CIRCULATION. PLUG AT 2490' WITH 270 SX CMT WITH PARTIAL RETURNS. NO CMT TO SURFACE. 3/4/14: TAG TOC IN 5 1/2" CASING AT 1200'. FLUID LEVEL @ 400'. RUN TBG TO 1170'. CIRCULATE CMT TO SURFACE WITH 130 SX CMT & 100# HULLS. TOP OFF WITH 20 SX CMT. CHECK ANNULUS. ANNULUS WAS FULL OF CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5141	5176		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

[Handwritten Signature]
3/20/14

(TECHNICIAN)

KCC WICHITA

MAR 14 2014

RECEIVED

RECEIVED

MAR 12 2014

KCC DODGE CITY

Form CP-2/3

[Handwritten mark]