

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20580-00-01
Spot: SWNENWNE Sec/Twnshp/Rge: 11-18S-43W
4854 feet from S Section Line, 1960 feet from E Section Line
Lease Name: NORMA WENDELBURG Well #: 2-11
County: GREELEY Total Vertical Depth: 5310 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2525		
CIBP		5070		WITH 2 SX CMT
DVT		2664		WITH 835 SX CMT
PROD	4.5	5310	0	WITH 310 SX CMT
SURF	8.625	268		WITH 175 SX CMT

Well Type: EOR UIC Docket No: E27144.4 Date/Time to Plug: 03/04/2014 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOE RUPP Company: VESS OIL Phone: (785) 798-5151

Proposed Plugging Method: CIBP @ 5100' WITH 2 SX CMT. CIBP @ 2650'. FILL WITH CMT TO SURFACE. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2014 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAKS 2930-3850. CIBP @ 5070' WITH 2 SX CMT. CIBP @ 2525' OVER CASING LEAKS. RAN TBG TO 2500'. CIRCULATED HOLE FULL OF CMT IN 2 STAGES USING 170 SX CMT & 150# HULLS. TOP OFF WITH 10 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
5167	5185		

KCC WICHITA

MAR 14 2014

RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
MAR 12 2014
KCC DODGE CITY

Signed

[Handwritten Signature]
(TECHNICIAN)
cc to UIC 3/17/14
3/22/14

[Handwritten initials]