

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20631-00-00
Spot: W2E2SESW Sec/Twnshp/Rge: 30-19S-39W
660 feet from S Section Line, 2150 feet from W Section Line
Lease Name: BUEHNE TRUST Well #: 2-30
County: GREELEY Total Vertical Depth: 2883 feet

Operator License No.: 32920
Op Name: W. R. WILLIAMS, INC.
Address: PO BOX 15163
AMARILLO, TX 79105

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2883	0	WITH 800 SX CMT
SURF	8.625	356		WITH 285 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/11/2014 9:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DEKE DANIELS Company: W.R. WILLIAMS Phone: (620) 376-8818

Proposed Plugging Method: Fill 4-1/2" casing with cement to surface. Fill 8-5/8"/4-1/2" annulus with cement to surface.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2014 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2846' TO 0' USING 215 SX CMT WITH 400# HULLS. PRESSURE TO 400#. HOLDING. PUMP 10 SX CMT DOWN THE ANNULUS TO 350#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2832	2846		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)
3/11/14

RECEIVED
MAR 12 2014
KCC DODGE CITY

KCC WICHITA
MAR 14 2014
RECEIVED

[Handwritten initials]