

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25561-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 2-19S-15W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: COBB Well #: 2
County: BARTON Total Vertical Depth: 3700 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3697		180 SX
SURF	8.625	940		400 SX
T1	2.375	3674		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/12/2014 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2014 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off bottom and topped with cement. Cut casing at 2792'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 950' and pumped 75 sx cement w/100 # hulls. Pulled casing to 450'. Circulated cement to surface with 100 sx cement and 100 # hulls. Pulled casing. Hole stayed full.

GPS: 38.42800 -098.94898

Perfs:

Top	Bot	Thru	Comments
3609	3615		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA

MAR 10 2014

RECEIVED

District: 04

Signed Bruce Rodie
3/27/14 (TECHNICIAN)

CM

FEB 24 2014