

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20423-00-00  
Spot: S2S2SW Sec/Twnshp/Rge: 3-20S-11W  
330 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: K SCHEUFLER Well #: 1-V  
County: BARTON Total Vertical Depth: 3301 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3300		75 SX
SURF	8.625	216		185 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/20/2014 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/20/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off bottom and topped with cement.  
Cut casing at 1614' and pulled to 1260'. Pumped 125 sx cement w/200 # hulls. Pulled casing to 850' and pumped 50 sx cement w/100 # hulls. Pulled casing to 500' and pumped 40 sx cement w/100 # hulls. Pulled casing to 200'. Circulated cement to surface with 75 sx cement. Pulled casing. Topped off with 25 sx cement.

GPS: 38.33357 -098.53014

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA  
MAR 10 2014  
RECEIVED

District: 04

Signed Bruce Rodie  
03/24/14 (TECHNICIAN) CM

FEB 24 2014