

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23662-00-01  
Spot: SWSWSE Sec/Twnshp/Rge: 14-19S-15W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: EBERLY Well #: 4  
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 31093  
Op Name: BECKER OIL CORPORATION  
Address: PO BOX 1150  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3459		200 SX
SURF	8.625	862		375 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2014 11:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DOUG BROWN Company: BECKER OIL CORP Phone: (620) 287-4724

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2014 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded back bottom to 3140' and set CIBP plug at 1760'. Cut pipe at 1500'. Pulled casing to 1460' and pumped 125 sx cement w/200 # hulls. Pulled casing to 975' and pumped 50 sx cement w/110 # hulls. Pulled casing to 500' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250' and pumped 125 sx cement. Cement circulated. POOH and cellar stayed full. Pulled 37 joints of 4 1/2" casing leaving 1959' of casing in the hole.

GPS: 38.39157 -098.94861

Perfs:

Top	Bot	Thru	Comments
3203	3376		
2243	2249		NEVA
2196	2205		COTTONWOOD
1870	1879		
1818	1828		
1802	1810		
1776	1784		
1756	2249		

KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

MAR 19 2014

Plugged through: CSG

RECEIVED

District: 04

Signed Ray A. Dinkel  
3/20/14 (TECHNICIAN)

CM

MAR 14 2014