

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-01007-00-01  
Spot: NENW Sec/Twnshp/Rge: 26-19S-22W  
4620 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: DORSA 26 Well #: 1  
County: NESS Total Vertical Depth: 4476 feet

Operator License No.: 8996  
Op Name: MID-CONTINENT RESOURCES, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1497		WITH 405 SX CMT
PROD	5.5	4475	0	WITH 530 SX CMT
SURF	8.625	325		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2014 3:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: SCOTT CORSAIR Company: MID-CONTINENT RESOURCES Phone: (620) 275-2963

Proposed Plugging Method: PUMP 75 SX CMT & 300# HULLS THEN GEL SPACER TO ANHYDRITE THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/14/2014 4:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

PUMPED 75 SX CMT & 300# HULLS, THEN GEL TO 1500' THEN 140 SX CMT. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 500# & HELD.

KCC WICHITA  
MAR 13 2014  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
2/24/14 (TECHNICIAN)

RECEIVED  
FEB 25 2014  
KCC DODGE CITY