

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-20226-00-02  
Spot: NWSESENE Sec/Twnshp/Rge: 22-14S-28W  
3225 feet from S Section Line, 598 feet from E Section Line  
Lease Name: COBBEE UNIT Well #: 3-1  
County: GOVE Total Vertical Depth: 4219 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4219		100 SX
SURF	8.625	308		250 SX

Well Type: EOR UIC Docket No: E26559.1 Date/Time to Plug: 02/26/2014 10:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERTSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed	Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Plugging	Perforations at 3914' - 3920', 3940' - 3945', 3978' - 3984', 4153' - 4158', 4126' - 4132' and 4144' - 4147'.
Method:	Squeezed at 1150' w/200 sx cement and 950' w/250 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/26/2014 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3905' and pumped 75 sx cement w/225 # hulls. Pulled tubing to 2928' and pumped 100 sx cement w/225 # hulls. Pulled tubing to 1529' and pumped 85 sx cement w/225 # hulls. Pulled tubing out. Squeezed casing w/65 sx cement. Shut in pressure 350 psi. Tied on to back side with instant pressure at 200 psi.

GPS: 38.82369 -100.41195

Perfs:

Top	Bot	Thru	Comments
4153	4158		
4144	4147		
4126	4132		
3978	3984		
3940	3945		
3914	3920		

KCC WICHITA

Remarks: SWIFT CEMENT CO TICKET # 25338

MAR 10 2014

Plugged through: TBG

RECEIVED

District: 04

Signed [Signature]  
(TECHNICIAN) CM  
cc to UIC 3/24/14  
3/24/14

MAR 06 2014