

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00973-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 33-5S-20W  
990 feet from N Section Line, 330 feet from W Section Line  
Lease Name: HANSEN Well #: B-1  
County: PHILLIPS Total Vertical Depth: 3584 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3568		125 SX
SURF	10.75	161		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2014 11:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 689-7567

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Production perforations: 3568' - 3584'.  
Casing leak: 1194' - 1225'  
Squeezed at 1102' w/100 sx cement

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2014 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1750' and 200'.  
Ran tubing to 3558' and pumped 200 sx cement w/300 # hulls. Pulled tubing to 1870' and pumped 150 sx cement w/200 # hulls to circulate to surface. Pulled all tubing. Hooked to 5 1/2" casing and pumped 100 sx cement to fill 10 3/4" x 5 1/2" annulus. Topped off 5 1/2" casing.  
GPS: 39.57916N -099.58917W

Perfs:

Top	Bot	Thru	Comments
3568	3584		

Remarks: SWIFT SERVICES TICKET # 25397

Plugged through: TBG

KCC WICHITA

MAR 21 2014

RECEIVED

District: 04

Signed Pat Bedore  
3/24/14 (TECHNICIAN)

CM

MAR 11 2014

MAR 18 2014